

Vassar Brother Hospital – UST Removals

Winter 2018



While performing demolition activities on the site in the location of the central utility plant in support of the \$545M patient Pavilion Expansion, Highground encountered three abandoned USTs. The three 12,000 gallons USTs were full of water and encased in concrete.

Approximately 30,000 gallons of contaminated water was pumped and transported off site to an approved disposal facility. Highground used a PC 400 with a Hydraulic hammer to remove the concrete to free up the tanks. Tanks were removed, cleaned, and recycled. During the remediation efforts, approximately 950 tons of contaminated soil and concrete was generated for offsite disposal.

Highground was able to navigate through some challenging conditions with the time of year and multiple trades working on the expansion project and still completed the project in a timely fashion.



Highground Industrial

1 International Blvd, Mahwah, NJ 07495 • 12 Industrial Drive, Florida, New York 10921
Main: (201) 252-8600 • Fax: (845) 651-1950 • Toll Free: 1-855-838-3366